BRUHATH BANGALORE MAHANAGARA PALIKE,
Office of the Executive Engineer, Dasarahalli Division
Schedule - B

AME OF THE WORK: **Construction of RCC drains at 1st cross in Ravindra Nagara nd other roads in ward no. 13 Shettyhalli sub division Division**

Sl No	Description of work	Unit	Qty	Approved Rates	
				In Figures (Rs.)	In Words (Rs.)
1	Earthwork excavation by manual means in ordinary soil involving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods Complete Asper the Directon Of Enggineer -in-charge of the work	CUM	236.52	200.00	Two Hundred
2	Removing B S Slab Drain And Stacking Asper the Directon Of Enggineer -in-charge of the work	SQM	394.20	70.00	Seventy
3	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing Asper the Directon Of Enggineer -in-charge of the work	CUM	34.78	4500.00	Four Thousand Five Hundred
4	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing Asper the Directon Of Enggineer -in-charge of the work	CUM	4.64	5250.00	Five ThousandTwo Hundred Fifty
5	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.43cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing Asper the Directon Of Enggineer -in-charge of the work	CUM	105.12	5900.00	Five Thousand nine Hundred
6	Providing and removing centering, shuttering, strutting,. propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached1 pilasters, buttresses, plinth cills and string courses cost of all materials, labour Asper the Directon Of Enggineer -in-charge of the work	SQM	1051.20	330.00	Three Hundred Thirty

EXECUTIVE ENGINEER - 2,
Bruhat Bangalore Mahanagara Palike,
Dasarahalli Division, Bangalore-57.

Scanned by CamScanner

7	Providing TMT steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design. Cost, hooks and wastage shall not be measured and paid. Cost of materials, labour, MDH of machinery Asper the Direction Of Engineer -in-charge of the work.	Tonne	6.31	67000.00	
8	Providing & laying reinforced cement precast slabs of min. Gr. 1:1:0.5:3 using 20mm & down size graded Granite metal using M20 (20mm dia steel @ 100mm c/c both ways & Asper the Direction Of Engineer -in-charge of the work.	Sqm	13.50	1700.00	One Thousand Seven Hundred

Signature of the Contractor

EXECUTIVE ENGINEER
Bruhat Bangalore Mahanagara Palike
Dasarahalli Division, Bangalore